

**GPS #:** 6613R1

Date Destroyed:

Date Revised: 1/29/2004

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 830/J-3

City / Location: Irvine

Scale Factor: 0.99997612

Ellipsoid Red. Factor: 0.99999529

Combination Factor: 0.99997141

Convergence Angle: -00 49 49.04218

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 51.90505	117 45 39.39323	2206908.289	6102201.542	
2007.00	33 42 51.92130	117 45 39.40904	2206909.95	6102200.23	

References: MM 517/46-47, RSB 150/24-35, CR 2003-0014

## Description:

FD TAG STAMPED "CITY OF IRVINE" SET IN HOLE IN CONC. DOWN 0.5' IN WELL MONUMENT. MONUMENT WAS RESET PER CORNER RECORD #2003-14A IN LIEU OF NAIL AND TAG IN CONC., "LS 3109", DOWN 1.65' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF IRVINE BLVD. (NW'LY) AND YALE AVE., 5.00' NE'LY FROM ANOTHER WELL MONUMENT.

