

GPS #: 6618

Date Destroyed:

Date Revised: 3/13/2012

Benchmark Designation: 3V-13-92

OCS Index Map: 6LC

Page/Grid: 832/G-2

City / Location: Silverado Cyn

Scale Factor: 0.99998002

Ellipsoid Red. Factor: 0.99994282

Combination Factor: 0.99992284

Convergence Angle: -00 45 21.75410

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 44 48.22147	117 37 32.98825	2218095.942	6143440.771	1195.060
2007.00	33 44 48.23789	117 37 33.00407	2218097.62	6143439.45	

References: OCS FILE #1112PW-RD560003, GEODETIC UNIT

Description:

FD 3-3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3V-13-92", SET IN THE NORTHWESTERLY CORNER OF A 20 FT. WIDE REINFORCED CONCRETE BOX. MONUMENT IS LOCATED ALONG THE SOUTHERLY SIDE OF SILVERADO CANYON ROAD, 2.95 MILES EASTERLY ALONG SILVERADO FROM THE CENTERLINE OF BLACK STAR CANYON AND 15 FT. SOUTHERLY OF THE CENTERLINE OF SILVERADO. MONUMENT IS SET LEVEL WITH THE ROAD.

