

GPS #: 6620R1

Date Destroyed:

Date Revised: 5/7/2003

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 861/A-1

City / Location: Irvine

Scale Factor: 0.99997532

Ellipsoid Red. Factor: 0.99999328

Combination Factor: 0.99996860

Convergence Angle: -00 49 29.27015

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 26.77059	117 45 03.41253	2204324.036	6105204.046	
2007.00	33 42 26.78706	117 45 03.42851	2204325.72	6105202.72	

References: RSB 118/21-23, RSB 150/24-35 CR 2003-1083

Description:

FD 2" IP WITH NAIL AND TAG, ILLEGIBLE, DOWN 1.6' IN WELL MONUMENT IN LIEU OF PUNCHED SPIKE AND O.C.S. WASHER. MONUMENT WAS RESET PER CORNER RECORD # 2003-1083 STATION IS LOCATED AT CENTERLINE INTERSECTION OF IRVINE BLVD. AND JEFFERY RD.

