

GPS #: 6622R1

Date Destroyed:

Date Revised: 2/27/2001

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 860/J-2

City / Location: Irvine

Scale Factor: 0.99997409

Ellipsoid Red. Factor: 0.99999636

Combination Factor: 0.99997045

Convergence Angle: -00 49 51.23224

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

| Epoch Adjustment | Latitude | Longitude | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35 | 33 41 46.93233 | 117 45 43.37863 | 2200346.357 | 6101769.680 | |
| 2007.00 | 33 41 46.94870 | 117 45 43.39467 | 2200348.03 | 6101768.35 | |

References: CR 0920, RSB 150/24-35

Description:

FD PUNCHED SPIKE AND OCS BRASS TAG STAMPED "RESET GPS 6622 1-95" FLUSH IN AC IN LIEU OF PUNCHED SPIKE AND "DOT" WASHER. MONUMENT WAS RESET PER CORNER RECORD # 920. STATION IS LOCATED ALONG THE CENTERLINE OF OLD TRABUCO RD. AND 15.00' NW'LY FROM ITS INTER WITH THE CENTERLINE OF JEFFREY RD.

