

**GPS #:** **6635R1**

Date Destroyed:

Date Revised: 2/1/2016

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 861/B-4

City / Location: Unin., Orange County

Scale Factor: 0.99997307

Ellipsoid Red. Factor: 0.99999313

Combination Factor: 0.99996620

Convergence Angle: -00 49 24.77632

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

| Epoch Adjustment | Latitude       | Longitude       | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35          | 33 41 13.37059 | 117 44 55.23473 | 2196895.541   | 6105788.192  |                       |
| 2007.00          | 33 41 13.38702 | 117 44 55.25079 | 2196897.22    | 6105786.86   |                       |

References: RSB 118/21-23, RSB 150/24-35, CR 2008-3361, CR 2013-2201

**Description:**

FD SPIKE AND WASHER STAMPED "LS 7845", FLUSH, IN LIEU OF PUNCHED HEX BOLT, DOWN 1.27' IN WELL MONUMENT. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF TRABUCO RD. AND SAND CANYON AVE.

