

GPS #: 6647

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 891/B-1

City / Location: Irvine

Scale Factor: 0.99997021

Ellipsoid Red. Factor: 0.99999527

Combination Factor: 0.99996547

Convergence Angle: -00 49 27.70513

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 33.34914	117 45 00.56453	2186792.890	6105192.416	98.956
2007.00	33 39 33.36597	117 45 00.58098	2186794.61	6105191.05	

References: PMB 239/9-16, RSB 150/24-35

Description:

FD PUNCHED 3" BRASS CAP, DOWN 1.49' IN WELL MONUMENT WITH FOUR 2' NAIL AND TAGS STAMPED "LS 4453". STATION IS LOCATED AT CENTERLINE INTER OF BARRANCA PKWY. AND IRVINE CENTER DR.

