

GPS #: 6648R1

Date Destroyed:

Date Revised: 9/21/2007

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 891/A-1

City / Location: Irvine

Scale Factor: 0.99996997

Ellipsoid Red. Factor: 0.99999529

Combination Factor: 0.99996526

Convergence Angle: -00 49 44.75797

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 24.67803	117 45 31.59694	2185954.355	6102556.952	
2007.00	33 39 24.69480	117 45 31.61344	2185956.07	6102555.58	

References: CR 0919, RSB 150/24-35

Description:

FD 2" I.P. WITH A PUNCHED SPIKE AND 1 1/2" OCS BRASS TAG STAMPED "RESET GPS 6648 1-95" DOWN 0.5' IN GRASS MEDIAN ISLAND IN LIEU OF 1" IP WITH PLASTIC PLUG STAMPED "LS 4_38". MONUMENT WAS RESET PER CORNER RECORD # 0919. STATION IS LOCATED ALONG THE GRASS MEDIAN OF ALTON PKWY., 396' +/- SOUTHEASTERLY FROM THE INTERSECTION OF ALTON PKWY. AND BANTING.

