

GPS #: **6650R1**

Date Destroyed:

Date Revised: 4/27/2001

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 861/C-7

City / Location: Irvine

Scale Factor: 0.99997037

Ellipsoid Red. Factor: 0.99999352

Combination Factor: 0.99996389

Convergence Angle: -00 49 09.22971

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 39.05661	117 44 26.94336	2187328.982	6108042.246	
2007.00	33 39 39.07343	117 44 26.95971	2187330.70	6108040.89	

References: RSB 150/24-35, CR 2001-0853

Description:

FD PUNCHED SPIKE AND 1 1/2" BRASS OCS WASHER STAMPED "6650R1 04/01" FLUSH, IN LIEU OF PK NAIL. MONUMENT WAS RESET PER CORNER RECORD # 2001-853. MONUMENT IS LOCATED ALONG THE VISUAL CENTERLINE OF BARRANCA PKWY., 0.15 MILE E'LY FROM TECHNOLOGY DR. TO AN INTER WITH AN UNNAMED ST.

