

GPS #: **6668R1**

Date Destroyed:

Date Revised: 6/12/2008

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 891/F-2

City / Location: Irvine

Scale Factor: 0.99996883

Ellipsoid Red. Factor: 0.99998791

Combination Factor: 0.99995675

Convergence Angle: -00 48 10.43150

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 42.04071	117 42 39.94370	2181438.383	6117004.712	
2007.00	33 38 42.05741	117 42 39.95971	2181440.09	6117003.38	

References: PMB 242/41-43, RSB 150/24-35, CR 97-203, CR 2001-0854, CR 2006-0747, CR 2008-0112

Description:

FD BRASS NAIL AND OCS TAG IN EPOXY, FLUSH, MONUMENT WAS RESET PER CR 2001-0854 PREVIOUS MONUMENT BEING; BRASS NAIL AND BRASS TAG STAMPED "LS 5301" SET IN EPOXY ON TOP OF GEARSPIKE PER CR 97-0203. STATION IS LOCATED AT CENTERLINE INTERSECTION OF JERONIMO RD. AND BAKE PKWY. NOTE: MONUMENT DESCRIPTION ON CORNER RECORD # 2001-0854 IS INCORRECT. TAG IS "LS 5301", NOT OCS TAG.

