

GPS #: **6672**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 832/D-7

City / Location: Unin., Orange County

Scale Factor: 0.99997617

Ellipsoid Red. Factor: 0.99994772

Combination Factor: 0.99992389

Convergence Angle: -00 46 01.72820

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 53.33214	117 38 45.73222	2206565.426	6137143.211	1092.622
2007.00	33 42 53.34871	117 38 45.74803	2206567.12	6137141.90	

References: A/5-7,6&8 52, RSB 150/24-35, CR 1292

Description:

FD 2 1/4" O.C.S. BRASS CAP, STAMPED "BC 6-1974", DOWN 1.90' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE BEGINNING OF CURVE ALONG SANTIAGO CANYON RD., 1.45 MILES NW'LY FROM ITS INTER WITH MODJESKA GRADE RD. AND 0.1 MILE SE'LY OF MODJESKA CANYON RD.

