

**GPS #:** **6673**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 862/E-1

City / Location: Unin., Orange County

Scale Factor: 0.99997527

Ellipsoid Red. Factor: 0.99994046

Combination Factor: 0.99991573

Convergence Angle: -00 45 54.69590

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 24.99614	117 38 32.93501	2203686.993	6138185.876	1244.282
2007.00	33 42 25.01265	117 38 32.95087	2203688.68	6138184.56	

References: A/5-7,6&8 49, RSB 150/24-35, CR 1292

**Description:**

FD PUNCHED 2 1/4" O.C.S. BRASS CAP DISK, STAMPED "EC 6-1974", DOWN 1.85' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE E.C. ALONG SANTIAGO CANYON RD., 0.95 MILE NW'LY FROM ITS INTER WITH MODJESKA CANYON RD.

