

GPS #: 6676

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 891/F-1

City / Location: Irvine

Scale Factor: 0.99996968

Ellipsoid Red. Factor: 0.99998869

Combination Factor: 0.99995837

Convergence Angle: -00 48 17.18450

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 13.75014	117 42 52.23263	2184657.812	6116010.921	236.322
2007.00	33 39 13.76673	117 42 52.24879	2184659.51	6116009.58	

References: PMB 185/1-3, RSB 150/24-35, CR 2003-0006

Description:

FD PUNCHED 2 1/2" BRASS DISK, STAMPED "RCE 21687", DOWN 1.43' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF ALTON PKWY. AND MORGAN.

