

**GPS #:** 6677

Date Destroyed:

Date Revised: 7/20/2010

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 891/G-3

City / Location: Lake Forest

Scale Factor: 0.99996842

Ellipsoid Red. Factor: 0.99998725

Combination Factor: 0.99995567

Convergence Angle: -00 47 55.00751

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 26.09407	117 42 11.87545	2179793.504	6119354.907	266.354
2007.00	33 38 26.11077	117 42 11.89153	2179795.21	6119353.57	

References: MM 456/16-20, RSB 150/24-35, CR 2010-0887

**Description:**

FD PUNCHED 2" O.C.S. BRASS DISK, STAMPED "11-74", DOWN 1.56' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF LAKE FOREST DR. AND JERONIMO RD.

