

GPS #: 6678

Date Destroyed:
Date Revised: 9/16/2009
Benchmark Designation:
OCS Index Map: 5LB
Page/Grid: 891/F-4
City / Location: Lake Forest

Scale Factor: 0.99996783
Ellipsoid Red. Factor: 0.99998897
Combination Factor: 0.99995680
Convergence Angle: -00 48 07.85573

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 03.02070	117 42 35.25636	2177489.109	6117345.721	230.423
2007.00	33 38 03.03763	117 42 35.27262	2177490.84	6117344.37	

References: A/6-8 2463, RSB 150/24-35, CR 2008-3045, CR 2009-0458

Description:

FD PUNCHED 2" O.C.S. BRASS DISK, STAMPED "6-74", DOWN 1.40' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF LAKE FOREST DR. AND MUIRLANDS BLVD.

