

GPS #: 6687

Date Destroyed:

Date Revised: 1/11/2012

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 862/C-6

City / Location: Lake Forest

Scale Factor: 0.99997122

Ellipsoid Red. Factor: 0.99996952

Combination Factor: 0.99994074

Convergence Angle: -00 46 32.10403

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 40 09.54615	117 39 41.00952	2190074.225	6132250.127	637.007
2007.00	33 40 09.56285	117 39 41.02525	2190075.93	6132248.82	

References: MM 657/26-32, RSB 150/24-35, CR 2011-2863, CR 2012-1382

Description:

RECOVERED 1/11/2012 PER CR 2011-2863 - ORIGINAL DESCRIPTION BEING: FD PUNCHED SPIKE AND WASHER, STAMPED "LS 4965", FLUSH. STATION IS LOCATED AT THE CENTERLINE INTER OF LAKE FOREST DR. AND RANCHO PKWY.

