

GPS #: 6708

Date Destroyed: 5/16/1997

Date Revised:

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 862/D-7

City / Location: Lake Forest

Scale Factor: 0.99997026

Ellipsoid Red. Factor: 0.99997000

Combination Factor: 0.99994026

Convergence Angle: -00 46 14.76805

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 35.12094	117 39 09.46190	2186558.865	6134869.374	626.875
2007.00	33 39 35.13773	117 39 09.47746	2186560.58	6134868.08	

References: RSB 150/36-50

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED SPIKE AND O.C.S. WASHER, STAMPED "85 PI", FLUSH. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF EL TORO RD. AND SANTA MARGARITA PKWY.

NO
LOCATION
MAP