

GPS #: 6717

Date Destroyed: 7/25/2000

Date Revised:

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 830/E-7

City / Location: Irvine

Scale Factor: 0.99997582

Ellipsoid Red. Factor: 1.00000244

Combination Factor: 0.99997826

Convergence Angle: -00 51 07.96962

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 42.27011	117 48 03.02363	2206112.622	6090055.490	-51.040
2007.00	33 42 42.28661	117 48 03.04039	2206114.31	6090054.10	

References: PMB 265/38-42, RSB 150/24-35

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED 3 1/4" ALUMINUM CAP, STAMPED "LS 4215", DOWN 1.31' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF JAMBOREE RD. AND WALNUT AVE.