

GPS #: 6748

Date Destroyed:

Date Revised: 6/24/2013

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 860/A-5

City / Location: Irvine

Scale Factor: 0.99997255

Ellipsoid Red. Factor: 1.00000373

Combination Factor: 0.99997628

Convergence Angle: -00 52 15.66124

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 40 55.79177	117 50 06.20735	2195507.440	6079487.050	-77.933
2007.00	33 40 55.80829	117 50 06.22424	2195509.13	6079485.65	

References: MM 313/20-22, RSB 150/24-35, CR 2011-0803, CR 2013-0175

Description:

FD PUNCHED 2 1/2" BRASS DISK, (ILLEGIBLE), DOWN 1.55' IN WELL MONUMENT. ACCEPTED AS 2 1/2" BRASS CAP STAMPED "LS 3246" PER MM 313/20-22. STATION IS LOCATED AT CENTERLINE INTER OF MURPHY AVE. AND KELVIN AVE.

