

GPS #: 7500

Date Destroyed:

Date Revised: 10/10/2014

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 950/E-2

City / Location: Laguna Beach

Scale Factor: 0.99996126

Ellipsoid Red. Factor: 0.99999742

Combination Factor: 0.99995868

Convergence Angle: -00 51 08.62724

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 01.53870	117 48 04.22039	2147420.876	6089081.155	53.825
2007.00	33 33 01.55536	117 48 04.23692	2147422.58	6089079.78	

References: RSB 150/36-50, CR 2014-1351, RS 2017-1042

Description:

FD GEAR SPIKE WITH 1 1/2" ALUMINUM WASHER, STAMPED "LS 4653", FLUSH. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF SAN JOAQUIN ST. AND HILLCREST DR.

