

GPS #: 7509R1

Date Destroyed:

Date Revised: 2/3/2010

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 950/H-4

City / Location: Laguna Beach

Scale Factor: 0.99996022

Ellipsoid Red. Factor: 1.00000134

Combination Factor: 0.99996156

Convergence Angle: -00 50 16.46126

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 32 02.85866	117 46 29.28986	2141371.813	6097027.691	
2007.00	33 32 02.87534	117 46 29.30635	2141373.52	6097026.32	

References: RSB 150/36-50, CR 2009-3018

Description:

FD GEAR SPIKE AND WASHER STAMPED "PLS 7564", FLUSH IN LIEU OF GEAR SPIKE WITH 1 1/2" ALUMINUM WASHER, STAMPED "LS 4653", FLUSH IN A.C., STATION IS LOCATED AT APPARENT CENTERLINE INTER OF CATALINA ST. AND BROOKS ST.

