

**GPS #:** **7518**

**Date Destroyed:** **7/26/2000**

**Date Revised:**

**Benchmark Designation:**

**OCS Index Map:** **6LA**

**Page/Grid:** **971/J-7**

**City / Location:** **Dana Point**

**Scale Factor:** **0.99995665**

**Ellipsoid Red. Factor:** **1.00000407**

**Combination Factor:** **0.99996072**

**Convergence Angle:** **-00 47 36.22581**

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 27 45.14105	117 41 37.69692	2114973.920	6121347.150	-85.049
2007.00	33 27 45.15790	117 41 37.71302	2114975.64	6121345.81	

**References:** **MM 502/13-19, RSB 150/36-50**

**Description:**

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED SPIKE WITH 1 1/4" STEEL WASHER STAMPED "LS 3236", FLUSH IN A.C., STATION IS LOCATED AT CENTERLINE INTER OF DANA POINT HARBOR DR. AND ST. OF THE GOLDEN LANTERN.