

**GPS #:** 7519R1

Date Destroyed:

Date Revised: 1/29/2004

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 971/H-6

City / Location: Dana Point

Scale Factor: 0.99995673

Ellipsoid Red. Factor: 0.99999815

Combination Factor: 0.99995488

Convergence Angle: -00 47 52.84875

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 27 52.15843	117 42 07.94697	2115718.721	6118794.580	
2007.00	33 27 52.17525	117 42 07.96308	2115720.44	6118793.24	

References: MM 586/10-11, RSB 150/36-50CR 2003-1305

## Description:

FD GEAR SPIKE AND WASHER STAMPED "LS 6970". MONUMENT WAS RESET PER CORNER RECORD #2003-1305B IN LIEU OF 4 GEAR SPIKES WITH WASHERS STAMPED "RCE 21687", FLUSH IN A.C., USED AS 4' SWING TANGENT OVER TIES TO ESTABLISH PUNCH MARK ON MANHOLE COVER. STATION IS LOCATED AT CENTERLINE INTER OF ST. OF THE AMBER LANTERN AND SANTA CLARA AVE.

