

GPS #: 7520R1

Date Destroyed:

Date Revised: 4/24/2012

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 971/G-6

City / Location: Dana Point

Scale Factor: 0.99995692

Ellipsoid Red. Factor: 0.99999210

Combination Factor: 0.99994902

Convergence Angle: -00 48 00.80888

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 28 08.89337	117 42 22.43263	2117427.156	6117591.167	
2007.00	33 28 08.91022	117 42 22.44883	2117428.88	6117589.82	

References: RSB 131/22, RSB 150/36-50, CR 2011-3695

Description:

FD GEAR SPIKE WITH TAG STAMPED "LS 5411"
FLUSH PER CR 2011-3695 IN LIEU OF PUNCHED
BOLT SPIKE WITH 1 1/4" STEEL WASHER, STAMPED
"LS 3519", FLUSH IN A.C., STATION IS LOCATED AT
CENTERLINE INTER OF CHULA VISTA AVE. AND LA
CRESTA DR.

