

GPS #: 7522R1

Date Destroyed:

Date Revised: 2/27/2013

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 971/J-5

City / Location: Dana Point

Scale Factor: 0.99995724

Ellipsoid Red. Factor: 0.99999069

Combination Factor: 0.99994793

Convergence Angle: -00 47 39.56574

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 28 36.92684	117 41 43.77486	2120214.811	6120904.858	
2007.00	33 28 36.94376	117 41 43.79105	2120216.54	6120903.51	

References: MM 383/4-7, RSB 150/36-50, CR 2012-1695, CR 2012-2739

Description:

FD GEAR SPIKE AND WASHER STAMPED "LS 8686" FLUSH PER CR 2012-2739, IN LIEU OF PUNCHED SPIKE WITH 1 1/4" STEEL WASHER, STAMPED "LS 2921", FLUSH IN A.C., STATION IS LOCATED AT CENTERLINE INTER OF CHELTAM WAY AND SHERWOOD WAY.

