

**GPS #:** 7530R1

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 891/D-5

City / Location: Laguna Hills

Scale Factor: 0.99996700

Ellipsoid Red. Factor: 0.99999213

Combination Factor: 0.99995913

Convergence Angle: -00 48 45.35237

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 29.96399	117 43 43.49191	2174229.405	6111529.545	
2007.00	33 37 29.98095	117 43 43.50822	2174231.14	6111528.19	

References: MM 372/48-50, RSB 150/36-50, CR 2011-1786, CR 2011-3175

**Description:**

FD BRASS PIN AND TAG STAMPED "LS 5301" PER CR 2011-3175 IN LIEU OF BOLT SPIKE WITH CHISELED "+" IN TOP AND 1 1/4" BRASS WASHER, STAMPED "-- 3246" ("LS" ILLEGIBLE), FLUSH IN A.C., ACCEPTED AS SPIKE AND WASHER STAMPED "LS 3246" PER MM 372/48-50. STATION IS LOCATED AT RADIUS POINT OF EL PACIFICO DR. CUL-DE-SAC, 210.00' EAST OF CENTERLINE ALONG VERDUGO DR.

