

GPS #: 7538R1

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 891/E-5

City / Location: Laguna Hills

Scale Factor: 0.99996703

Ellipsoid Red. Factor: 0.99999138

Combination Factor: 0.99995841

Convergence Angle: -00 48 32.58395

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 31.23977	117 43 20.25623	2174330.543	6113495.969	
2007.00	33 37 31.25676	117 43 20.27258	2174332.28	6113494.61	

References: PMB 120/17-21, RSB 150/36-50, CR 2011-1820, CR 2011-3198

Description:

FD SPIKE AND WASHER STAMPED "LS 5310" PER CR 2011-3198 IN LIEU OF PUNCHED BOLT SPIKE AND WASHER, STAMPED "LS ----" ("3246" ILLEGIBLE), FLUSH IN A.C. ACCEPTED AS SPIKE AND WASHER STAMPED "LS 3246" PER PM 120/17-21. STATION IS LOCATED AT CENTERLINE INTER OF SOUTH POINTE DR. AND PLAZA POINTE DR.

