

GPS #: 7556

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 952/B-3

City / Location: San Juan Capistrano

Scale Factor: 0.99996037

Ellipsoid Red. Factor: 0.99999455

Combination Factor: 0.99995492

Convergence Angle: -00 46 59.97591

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 32 11.34541	117 40 31.73013	2141801.350	6127302.981	113.851
2007.00	33 32 11.36254	117 40 31.74615	2141803.10	6127301.65	

References: RSB 150/36-50

Description:

FD PUNCHED SPIKE AND 2 WASHERS (STACKED).
BOTTOM WASHER STAMPED "DIVISION OF HWY.S",
NO STAMPING ON TOP WASHER, UP 0.02' IN A.C.,
STATION IS LOCATED ALONG THE SHOULDER OF
CAMINO CAPISTRANO, 0.7+/- MILE S'LY OF AVERY
PKWY., 5.0'+/- W'LY OF TRAVELED WAY, IN A.C.
SHOULDER.

