

GPS #: 7561

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 971/G-1

City / Location: Laguna Niguel

Scale Factor: 0.99995848

Ellipsoid Red. Factor: 0.99999110

Combination Factor: 0.99994958

Convergence Angle: -00 48 02.46458

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 30 11.17265	117 42 25.44564	2129788.965	6117508.670	186.013
2007.00	33 30 11.18941	117 42 25.46188	2129790.68	6117507.32	

References: MM 452/32-35, RSB 150/36-50

Description:

FD PUNCHED 2" BRASS DISK, STAMPED "RCE 23956", DOWN 1.2' IN WELL MONUMENT. STATION IS LOCATED AT THE CENTERLINE BEGINNING OF CURVE ALONG BEACON HILL WAY, 114.60' E'LY FROM ITS CENTERLINE INTER WITH BELLINGHAM PLACE.

