

GPS #: 7565

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 951/E-6

City / Location: Laguna Niguel

Scale Factor: 0.99995943

Ellipsoid Red. Factor: 0.99997939

Combination Factor: 0.99993882

Convergence Angle: -00 48 31.46357

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 31 14.36453	117 43 18.21738	2136238.280	6113130.674	430.708
2007.00	33 31 14.38155	117 43 18.23343	2136240.02	6113129.34	

References: MM 566/43-48, RSB 150/36-50

Description:

FD PUNCHED BOLT SPIKE WITH 1 1/4" BRASS WASHER, STAMPED "LS 4693", FLUSH IN A.C., STATION IS LOCATED AT THE CENTERLINE B.C. ALONG MIRANDELA LN., 297.56' S'LY, AS MEASURED ALONG THE CENTERLINE, FROM ITS INTER WITH VIA ESTORIL.

