

GPS #: 7575

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 951/F-3

City / Location: Laguna Niguel

Scale Factor: 0.99996037

Ellipsoid Red. Factor: 0.99998729

Combination Factor: 0.99994766

Convergence Angle: -00 48 26.94273

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 32 11.55649	117 43 09.99044	2142008.649	6113908.569	265.705
2007.00	33 32 11.57354	117 43 10.00657	2142010.39	6113907.23	

References: RSB 150/36-50

Description:

FD TAG, STAMPED "LS 292_" (DIFFICULT TO READ), DOWN 1.4' IN O.C.S. WELL MONUMENT. ACCEPTED AS BRASS TAG STAMPED "LS 2921" PER MM 300/9-13. STATION IS LOCATED AT THE CENTERLINE E.C. ALONG THACKERY DR., 231.53' N'LY, AS MEASURED ALONG THE CENTERLINE, FROM ITS INTER WITH LOCHLOMAND DR.

