

GPS #: **7577R1**

Date Destroyed:

Date Revised: 9/20/2009

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 951/F-4

City / Location: Laguna Niguel

Scale Factor: 0.99996025

Ellipsoid Red. Factor: 0.99998879

Combination Factor: 0.99994904

Convergence Angle: -00 48 13.43660

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 32 04.61526	117 42 45.41228	2141277.870	6115978.949	
2007.00	33 32 04.63230	117 42 45.42828	2141279.61	6115977.62	

References: A/7-8 1666, RSB 150/36-50, CR 2008-2328, CR 2009-1470

Description:

FD SPIKE AND WASHER STAMPED "LS 5411", FLUSH IN LIEU OF PUNCHED SPIKE AND ALUMINUM O.C.S. WASHER FLUSH IN A.C.; ACCEPTED AS THE CENTERLINE B.C. ALONG ANA MARIA LN. AND FITS THREE OF THE FOUR TIES PER A/7-8 1666. MONUMENT IS LOCATED 396.21' SW'LY, AS MEASURED ALONG THE CENTERLINE, FROM ITS INTER WITH IVY GLENN DR.

