

GPS #: 7583

Date Destroyed:

Date Revised: 6/4/2001

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 951/H-6

City / Location: Laguna Niguel

Scale Factor: 0.99995938

Ellipsoid Red. Factor: 0.99998588

Combination Factor: 0.99994526

Convergence Angle: -00 47 49.77388

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 31 10.92913	117 42 02.35138	2135801.070	6119548.082	294.999
2007.00	33 31 10.94607	117 42 02.36741	2135802.80	6119546.75	

References: MM 572/1-3, RSB 150/36-50

Description:

FD 2" PUNCHED BRASS DISK STAMPED "RCE 23956", DOWN 1.5' IN O.C.S. WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF MARINA HILLS DR. AND PARC VISTA.

