

GPS #: 7587

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 952/A-6

City / Location: Laguna Niguel

Scale Factor: 0.99995928

Ellipsoid Red. Factor: 0.99998088

Combination Factor: 0.99994015

Convergence Angle: -00 47 10.32970

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 31 04.40032	117 40 50.57174	2135057.259	6125615.429	399.658
2007.00	33 31 04.41738	117 40 50.58761	2135059.00	6125614.11	

References: MM 542/25-28, RSB 150/36-50

Description:

FD GEAR SPIKE AND WASHER, STAMPED "RCE 23956", FLUSH IN A.C., STATION IS LOCATED AT CENTERLINE INTER OF CURACAO AND SAINT VINCENT.

