

GPS #: 7592

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 972/A-4

City / Location: Dana Point

Scale Factor: 0.99995733

Ellipsoid Red. Factor: 1.00000344

Combination Factor: 0.99996077

Convergence Angle: -00 47 11.49778

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 28 44.01867	117 40 52.69739	2120871.870	6125240.706	-71.972
2007.00	33 28 44.03551	117 40 52.71344	2120873.59	6125239.37	

References: MM 434/1-9, RSB 150/36-50

Description:

FD PUNCHED 2" BRASS DISK, STAMPED "RCE 23207", DOWN 1.15' IN O.C.S. WELL MONUMENT. STATION IS LOCATED AT CENTERLINE POINT OF REVERSE CURVE ALONG WHITE SANDS ST., 140.00' W'LY, AS MEASURED ALONG THE CENTERLINE, FROM ITS INTER WITH BREEZY PLACE.

