

**GPS #:** 7596

Date Destroyed:

Date Revised: 6/4/2001

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 951/H-4

City / Location: Laguna Niguel

Scale Factor: 0.99996019

Ellipsoid Red. Factor: 0.99998684

Combination Factor: 0.99994703

Convergence Angle: -00 47 43.48394

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 32 01.06445	117 41 50.90508	2140854.613	6120587.398	275.022
2007.00	33 32 01.08144	117 41 50.92107	2140856.35	6120586.07	

References: MM 219/18-23, RSB 150/36-50

**Description:**

FD PUNCHED 2" BRASS DISK, STAMPED "LS 2602", DOWN 0.82' IN TRIANGULAR WELL MONUMENT. STATION IS LOCATED AT CENTERLINE B.C. ALONG VISTA PLAZA DR., 325.82' SW'LY, AS MEASURED ALONG THE CENTERLINE, FROM ITS INTER WITH CALLE VIEJA.

