

GPS #: 7601

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 952/A-2

City / Location: Laguna Niguel

Scale Factor: 0.99996098

Ellipsoid Red. Factor: 0.99998974

Combination Factor: 0.99995072

Convergence Angle: -00 47 04.47170

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 32 46.14015	117 40 39.91147	2145327.435	6126658.691	214.448
2007.00	33 32 46.15721	117 40 39.92761	2145329.18	6126657.35	

References: MM 525/14-21, RSB 150/36-50

Description:

FD 2" PUNCHED BRASS DISK, STAMPED "RCE 23956", DOWN 1.26' IN O.C.S. WELL MONUMENT. STATION IS LOCATED AT CENTERLINE BEGINNING OF CURVE ALONG CHERREADAS, AT THE ST. ADDRESS #28691, 0.10+/- MILE SOUTH OF PASEO DE COLINAS.

