

GPS #: 7606

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 921/E-1

City / Location: Laguna Hills

Scale Factor: 0.99996514

Ellipsoid Red. Factor: 0.99998662

Combination Factor: 0.99995175

Convergence Angle: -00 48 29.23092

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 11.08802	117 43 14.15446	2166222.446	6113897.615	279.678
2007.00	33 36 11.10518	117 43 14.17064	2166224.20	6113896.27	

References: A/6-8 5961, RSB 150/36-50

Description:

FD PUNCHED 2 1/2" O.C.S. BRASS DISK, STAMPED "JAN 1990", DOWN 1.40' IN O.C.S. WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF CALLE CORTEZ AND VIA IGLESIA.

