

GPS #: 7608R1

Date Destroyed:

Date Revised: 2/1/2011

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 921/F-2

City / Location: Laguna Hills

Scale Factor: 0.99996456

Ellipsoid Red. Factor: 0.99999148

Combination Factor: 0.99995604

Convergence Angle: -00 48 19.71380

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 35 45.10469	117 42 56.83542	2163575.732	6115325.407	
2007.00	33 35 45.12179	117 42 56.85163	2163577.48	6115324.06	

References: MM 562/43-46, RSB 150/36-50, CR 2009-1965, CR 2009-2461

Description:

FD PUNCHED SPIKE AND 2 SMALLER WASHER STAMPED "LS 5301" FLUSH, IN LIEU OF PUNCHED SPIKE AND 1 1/2" BRASS WASHER, STAMPED "LS 3906", FLUSH IN A.C., STATION IS LOCATED AT CENTERLINE INTER OF GLENWOOD DR./INDIAN CREEK LN. AND NEW MOULTON PKWY.

