

GPS #: 7613

Date Destroyed:

Date Revised: 8/8/2006

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 921/H-3

City / Location: Laguna Hills

Scale Factor: 0.99996402

Ellipsoid Red. Factor: 0.99998362

Combination Factor: 0.99994765

Convergence Angle: -00 47 38.03160

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 35 20.78275	117 41 40.98306	2161028.007	6121706.904	342.234
2007.00	33 35 20.79991	117 41 40.99911	2161029.76	6121705.57	

References: MM 417/1-9, RSB 150/36-50, CR 2006-0283

Description:

FD PUNCHED SPIKE AND ALUMINUM WASHER, STAMPED "LS 3428", DOWN 0.13' IN A.C., STATION IS LOCATED AT CENTERLINE INTER OF LUNA BONITA DR. AND ENCANTO COURT.

