

GPS #: 7616

Date Destroyed:

Date Revised: 6/4/2001

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 921/G-6

City / Location: Laguna Niguel

Scale Factor: 0.99996225

Ellipsoid Red. Factor: 0.99999281

Combination Factor: 0.99995506

Convergence Angle: -00 47 52.58617

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 54.07950	117 42 07.46915	2152296.220	6119344.500	150.285
2007.00	33 33 54.09671	117 42 07.48515	2152297.98	6119343.17	

References: MM 613/45-46, RSB 150/36-50

Description:

FD PUNCHED SPIKE AND 1 1/4" BRASS WASHER, STAMPED "LS 4599" FLUSH IN A.C., STATION IS LOCATED AT THE CENTERLINE INTER OF MOULTON PKWY. AND ALISO NIGUEL.

