

GPS #: 7617R1

Date Destroyed:

Date Revised: 3/6/2013

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 921/G-7

City / Location: Laguna Niguel

Scale Factor: 0.99996193

Ellipsoid Red. Factor: 0.99999384

Combination Factor: 0.99995576

Convergence Angle: -00 47 59.38272

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 37.50941	117 42 19.83734	2150636.115	6118274.653	
2007.00	33 33 37.52657	117 42 19.85339	2150637.87	6118273.32	

References: MM 586/14-18, RSB 150/36-50, CR 2011-2084, CR 2012-3379

Description:

FD GEAR SPIKE AND WASHER STAMPED "LS 5411" FLUSH PER CR 2012-3379 IN LIEU OF, GEAR SPIKE AND WASHER, STAMPED "LS 4599", FLUSH IN A.C., STATION IS LOCATED AT CENTERLINE INTER OF NIGUEL HEIGHTS BLVD. AND GOLDRUSH RIDGE LN.

