

GPS #: 7626R1

Date Destroyed: 5/7/2013
Date Revised: 2/25/2013
Benchmark Designation:
OCS Index Map: 6LA
Page/Grid: 921/H-5
City / Location: Laguna Hills

Scale Factor: 0.99996279
Ellipsoid Red. Factor: 0.99999457
Combination Factor: 0.99995735
Convergence Angle: -00 47 49.37683

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 34 21.33057	117 42 01.62888	2155043.544	6119876.960	
2007.00	33 34 21.34775	117 42 01.64499	2155045.30	6119875.62	

References: MM 446/3-5, RSB 150/36-50, CR 2012-1952, CR 2012-3511

Description:

REPORTED DESTROYED PER CR 2000-203(SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED 2" BRASS DISK DOWN 1.7' IN WELL PER CR 2012-3511, IN LIEU OF, 2 1/2" ALUMINUM O.C.S. DISK, STAMPED "2-74", DOWN 1.5' IN O.C.S. WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF PACIFIC PARK DR. AND MOULTON PKWY.