

GPS #: 7627

Date Destroyed:

Date Revised: 6/24/2013

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 922/A-5

City / Location: Laguna Hills

Scale Factor: 0.99996319

Ellipsoid Red. Factor: 0.99997994

Combination Factor: 0.99994313

Convergence Angle: -00 47 07.21747

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 34 41.10226	117 40 44.90817	2156952.195	6126395.099	419.258
2007.00	33 34 41.11924	117 40 44.92440	2156953.93	6126393.75	

References: M 642/11-16, RSB 150/36-50, CR 2013-0902

Description:

FD GEAR SPIKE AND WASHER, STAMPED "RCE 23956", FLUSH IN A.C., STATION IS LOCATED AT CENTERLINE INTER OF BRIDLEWOOD DR. AND LAURELCREST DR.

