

GPS #: **7632**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 921/J-5

City / Location: Laguna Hills

Scale Factor: 0.99996305

Ellipsoid Red. Factor: 0.99998743

Combination Factor: 0.99995049

Convergence Angle: -00 47 31.10011

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 34 34.42360	117 41 28.36929	2156327.807	6122709.087	262.608
2007.00	33 34 34.44075	117 41 28.38537	2156329.56	6122707.75	

References: MM 419/29-44, RSB 150/36-50

Description:

FD PUNCHED 2" BRASS DISK, STAMPED "LS 2921", DOWN 1.28' IN O.C.S. WELL MONUMENT. STATION IS LOCATED AT CENTERLINE BEGINNING OF CURVE ALONG BUCKBOARD LN., 547.32' W'LY, AS MEASURED ALONG THE CENTERLINE, FROM ITS CENTERLINE INTER WITH NELLIE GAIL RD.

