

GPS #: 7641

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 922/D-6

City / Location: Mission Viejo

Scale Factor: 0.99996219

Ellipsoid Red. Factor: 0.99998486

Combination Factor: 0.99994706

Convergence Angle: -00 46 18.56698

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 51.19948	117 39 16.37511	2151806.825	6133816.807	316.302
2007.00	33 33 51.21638	117 39 16.39105	2151808.55	6133815.48	

References: MM 358/1-6, RSB 150/36-50

Description:

FD TACK AND TAG IN CONC., (ILLEGIBLE), DOWN 1.37' IN WELL MONUMENT. ACCEPTED AS TACK AND TAG STAMPED "LS 3109" PER MM 358/1-6. STATION IS LOCATED AT CENTERLINE POINT OF REVERSE CURVE ALONG JARDINES ST., 0.1+/- MILE NORTH OF CROWN VALLEY PKWY.

