

GPS #: 7650R1

Date Destroyed:

Date Revised: 2/25/2013

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 892/F-7

City / Location: Mission Viejo

Scale Factor: 0.99996603

Ellipsoid Red. Factor: 0.99997035

Combination Factor: 0.99993639

Convergence Angle: -00 45 43.02457

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 49.70155	117 38 11.69577	2169774.591	6139529.315	
2007.00	33 36 49.71837	117 38 11.71149	2169776.31	6139528.01	

References: MM 409/28-30, RSB 150/36-50, CR 2011-3775, CR 2012-1543

Description:

FD GEAR SPIKE AND WASHER STAMPED "LS 5411" FLUSH, PER CR 2012-1543, IN LIEU OF PUNCHED BOLT SPIKE WITH 1 1/4" BRASS WASHER, STAMPED "___ 14749" (PARTIALLY ILLEGIBLE), DOWN 0.02' IN A.C., ACCEPTED AS SPIKE WITH BRASS WASHER STAMPED "RCE 14749" PER MM 409/28-30. STATION IS LOCATED AT THE RADIUS POINT OF GITANO ST. CUL-DE-SAC, 0.20+/- MILE NORTH OF RAMONA ST.

