

GPS #: 7652

Date Destroyed:

Date Revised: 6/5/2001

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 922/E-1

City / Location: Mission Viejo

Scale Factor: 0.99996517

Ellipsoid Red. Factor: 0.99997488

Combination Factor: 0.99994004

Convergence Angle: -00 45 56.55772

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 12.38086	117 38 36.32311	2166030.379	6137396.344	525.012
2007.00	33 36 12.39771	117 38 36.33893	2166032.10	6137395.03	

References: MM 420/8-12, RSB 150/36-50

Description:

FD PUNCHED SPIKE WITH 1 1/4" BRASS WASHER, STAMPED "RCE 14749", FLUSH IN A.C., STATION IS LOCATED AT THE RADIUS POINT OF CLAVEL ST. CUL-DE-SAC, 64.00' WEST FROM ITS CENTERLINE INTER WITH LUCERO ST.

