

GPS #: 7667

Date Destroyed:

Date Revised: 6/5/2001

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 922/C-5

City / Location: Mission Viejo

Scale Factor: 0.99996305

Ellipsoid Red. Factor: 0.99998048

Combination Factor: 0.99994354

Convergence Angle: -00 46 30.06654

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 34 34.36717	117 39 37.30175	2156193.607	6132105.206	407.831
2007.00	33 34 34.38413	117 39 37.31757	2156195.34	6132103.89	

References: MM 363/15-21, RSB 150/36-50, CR 2001-0867

Description:

FD PUNCHED BOLT SPIKE WITH 1 1/4" BRASS WASHER, STAMPED "LS 3109", FLUSH IN A.C. STATION IS LOCATED AT END OF CENTERLINE, 15.00' W'LY FROM THE RADIUS POINT OF MARBELLA CUL-DE-SAC, 0.20+/- MILE N'LY FROM ITS INTER WITH NUBLADO.

