

GPS #: 7675R2

Date Destroyed:

Date Revised: 3/3/2008

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 952/B-1

City / Location: Laguna Niguel

Scale Factor: 0.99996148

Ellipsoid Red. Factor: 0.99999343

Combination Factor: 0.99995491

Convergence Angle: -00 46 57.00673

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 14.01244	117 40 26.32692	2148128.699	6127846.803	
2007.00	33 33 14.02949	117 40 26.34293	2148130.44	6127845.47	

References: RSB 150/36-50, CR 2001-0868, CR 2007-1430

Description:

FD PUNCH SPIKE AND 1 1/2" BRASS TAG, STAMPED "CALTRANS", FLUSH. IN LIEU OF PUNCHED SPIKE AND 1 1/4" OCS BRASS WASHER STAMPED "7675R1 4-01", FLUSH, MONUMENT WAS RESET PER CORNER RECORD # 2007-1430. STATION IS LOCATED AT THE VISUAL CENTERLINE B.C. ALONG CAMINO CAPISTRANO, 0.45+/- MILE N'LY FROM AVERY PKWY.

