

GPS #: 7676

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 922/D-3

City / Location: Mission Viejo

Scale Factor: 0.99996394

Ellipsoid Red. Factor: 0.99998021

Combination Factor: 0.99994416

Convergence Angle: -00 46 19.54460

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 35 17.01336	117 39 18.15416	2160481.926	6133783.162	413.490
2007.00	33 35 17.03024	117 39 18.17016	2160483.65	6133781.83	

References: MM 622/31-36, RSB 150/36-50

Description:

FD GEAR SPIKE WITH 1 1/4" STEEL WASHER, STAMPED "LS 5780", FLUSH IN A.C., STATION IS LOCATED AT THE CENTERLINE INTER OF PACIFIC HILLS DR. AND PACIFIC HEIGHTS DR.

